









PLANT SCHEDULE

| TREES | BOTANICAL / COMMON NAME | SIZE | WATER USE |
|-------------------------------------------------------------------------------------|-----------------------------------------------------------------|--------|-----------|
|  | ARBUTUS UNEDO / STRAWBERRY TREE MULTI-TRUNK | 24"BOX | LOW |
|  | ARBUTUS UNEDO / STRAWBERRY TREE STANDARD | 24"BOX | LOW |
|  | CITRUS X LIMON 'DWARF MEYER' / MEYER LEMON | 15 GAL | MEDIUM |
|  | OLEA EUROPAEA 'SWAN HILL' TM / SWAN HILL OLIVE | 24"BOX | LOW |
|  | PISTACIA CHINENSIS 'KEITH DAVEY' / KEITH DAVEY CHINESE PISTACHE | 24"BOX | LOW |
|  | QUERCUS WISLIZENII / INTERIOR LIVE OAK | 24"BOX | LOW |
|  | ULMUS PROPINQUA 'JFS-BIEBERICH' TM / EMERALD SUNSHINE ELM | 24"BOX | MEDIUM |




PRELIMINARY DESIGN REVIEW
MARCH 22, 2019, UPDATED OCTOBER 30, 2020



- KEY**
- 1"x6" FENCE BOARD PANELS.
 - 4"x4" PRESSURE TREATED WOOD POST. APPROXIMATELY 8' O.C.
 - THREE 2"x4" RAILS.
 - 1"x4" PLANT-ON BOARD.
 - 12"x24" CONCRETE FOOTING SLOPED TO DRAIN. CUT PANELS AROUND FOOTING.
 - FINISH GRADE.
 - UNDISTURBED NATIVE GRADE OR ENGINEERED FILL PER SOILS REPORT.
 - 2"x8" CAP.

NOTES

1. ALL WOOD SHALL BE CONSTRUCTION HRT. REDWOOD OR CEDAR #2 OR BETTER.
2. AIR POWERED GALVANIZED 6D OR 8D NAILS AT FENCE BOARDS, 16D GALVANIZED FRAME NAILS.
3. ALTERNATE PANEL SIDE AT EACH 8' SECTION OF FENCE. (WHERE ADJACENT TO OPEN SPACE PANELS TO FACE OUTWARD CONTINUOUSLY)



A ENHANCED WOOD FENCE WITH WOOD POST


WR-LA-FNC-17

KEY

- 3" x 12 GA. POST
- 1 3/4" x 14 GA. RAIL
- 1" x 14 GA. PICKET
- 18" x 30" CONCRETE FOOTING
- COMPACTED SUBGRADE TO 90% R.D.
- 4" AGGREGATE BASE, COMPACTED TO 95% R.D.
- FINISH GRADE

NOTES


1. ALL FENCE PARTS TO BE TUBULAR STEEL. GRIND SMOOTH ALL WELDS.
2. ALL METAL TO BE POWDERCOATED, COLOR: RAL #8017. CONTRACTOR TO SUBMIT SAMPLE TO LANDSCAPE ARCHITECT.
3. FIELD VERIFY ALL DIMENSIONS PRIOR TO CONSTRUCTION.



B 6" TUBE STEEL FENCE

NT.S.

WR-LA-FNC-07



KEY

- 1" x 6" FENCE BOARD PANELS
- MIN. 3" SQ. GALV. METAL POST. APPROX. 8' O.C.
- THREE 2"x4" RAILS
- 1"x6" PLANT-ON BOARD
- 12"x24" CONCRETE FOOTING SLOPED TO DRAIN. CUT PANELS AROUND FOOTING.
- FINISH GRADE
- UNDISTURBED NATIVE GRADE OR ENGINEERED FILL PER SOILS REPORT.
- 2"x8" CAP
- 6"x6" WOOD CAP. CONTRACTOR TO SUBMIT SAMPLE BEFORE ORDERING.
- 6"x6" WOOD POST @ END OF FENCE.
- 1" DRAIN ROCK, 4" DEPTH

NOTES

1. ALL WOOD SHALL BE CONSTRUCTION HRT. RO. REDWOOD OR CEDAR #2 OR BETTER. STAINED: SW 3542 CHARWOOD
2. ALL POSTS TO BE MASTER HALCO POSTMASTER WOOD FENCE POST. TO BE PAINTED RAL 8017
3. AIR POWERED GALVANIZED 6D OR 8D NAILS AT FENCE BOARDS, 16D GALVANIZED FRAME NAILS.
4. DO NOT ALTERNATE FENCE PANEL. WHERE ADJACENT TO OPEN SPACE, PANELS TO FACE OUTWARD.


C DELUXE FENCE W/ 6"x6" END CAP

NT.S.

P-SUNR-18

KEY


- 4" AGGREGATED BASE, COMPACTED TO 95% R.D.
- COMPACTED SUBGRADE TO 90% R.D.
- PRE-EMERGENT WEED CONTROL.



D COMPACTED AGGREGATE TRAIL

NT.S.

P-CP-01



E CLASS 1 TRAIL - LOT C

NT.S.